

SOP-FW-002 REV 1: Weekly Fire Water Pump Test - Unit 4

Standard Operating Procedure SOP-FW-002 Revision: 1 Effective date: 2019-02-01
Title: Weekly Fire Water Pump Test - Unit 4

PROCEDURE STEPS:

1. Notify control room.
2. Auto-start test on pressure drop simulation.
3. Record jockey/main/diesel pump start pressures.
4. Run main pump 30 min; log header pressure (target ≥ 8.5 kg/cm² per OISD-STD-116).
5. Restore auto lineup.

HAZARDS: High pressure water; rotating equipment.

Approved by: Plant Manager, Unit 4