

SOP-HW-001 REV 3: Hot Work Permit Procedure - Unit 4

Standard Operating Procedure SOP-HW-001 Revision: 3 Effective date: 2022-01-05

Title: Hot Work Permit Procedure - Unit 4

Supersedes: SOP-HW-001 rev 2

PROCEDURE STEPS:

1. Gas test at worksite; LEL must be 0% for welding in Area 3.
2. Fire watch posted with extinguisher.
3. Screens and drain covers in place.
4. Permit valid one shift only; revalidate after breaks.
5. Post-work fire watch 30 min.

HAZARDS: Ignition of hydrocarbon vapors.

Approved by: Plant Manager, Unit 4