

SOP-MOV-004 REV 1: MOV-110 Operation and Partial Stroke Test

Standard Operating Procedure SOP-MOV-004 Revision: 1 Effective date: 2016-09-12
Title: MOV-110 Operation and Partial Stroke Test

PROCEDURE STEPS:

1. Confirm CW system lineup allows brief flow disturbance.
2. Initiate partial stroke from panel; observe torque curve.
3. Full stroke annually during shutdown only.
4. Record stroke time and torque signature.

HAZARDS: Flow transient; pinch points.

Approved by: Plant Manager, Unit 4