

SOP-TK-014 REV 1: Manual Gauging & Sampling of T-301 / T-302

Standard Operating Procedure SOP-TK-014 Revision: 1 Effective date: 2020-06-10
Title: Manual Gauging & Sampling of T-301 / T-302

PROCEDURE STEPS:

1. Verify tank not receiving/dispatching.
2. Bond sampling equipment; use only conductive tape.
3. Wait 30 min after any transfer before gauging (static electricity).
4. Record level, temperature, water cut.
5. Close gauge hatch fully.

HAZARDS: Flammable atmosphere at gauge hatch; static discharge.

Approved by: Plant Manager, Unit 4